

Proposed Integrated Watershed TMDL Indicator and Dashboard Products

Gary Shenk, Qian Zhang, Gopal Bhatt, Isabella Bertani, Chris Mason,
Doug Moyer, Peter Tango

WQGIT


11/14/2022

Purpose of presentation

- Build understanding
- Get feedback
 - This is not your last chance for feedback!
- Make progress toward an approved indicator and data dashboard product

Tidal Water TMDL Indicator

Very slow
positive change



WIP Indicator

We've almost hit the target level of implementation?



Modeled Nitrogen Loads to the Chesapeake Bay (1985-2021)


Loads simulated using CAST19 and jurisdiction-reported data on wastewater discharges. *The natural sector wetlands which are preferable land use types with the lowest loading rates among sources.

[VIEW CHART](#)

[VIEW TABLE](#)

Loads by Source

Loads by Jurisdiction



Nontidal Load Indicator

Extreme variability
No Clear Trend

Pollution Loads and River Flow to the Chesapeake Bay (1990-2019)

River and Watershed Input of Pollution Loads


[VIEW CHART](#)




[VIEW TABLE](#)

Nitrogen Loads

Phosphorus Loads

Sediment Loads





Differences due to:

- Averaging periods
- Lag times
- Temperature effects
- Errors in both estimates

Differences due to:


- Normalization for flow
- Lag times
- Non-management factors
- Errors in both estimates

Ator, S.W., Blomquist, J.D., Webber, J.S. and Chanat, J.G., 2020. Factors driving nutrient trends in streams of the Chesapeake Bay watershed. *Journal of Environmental Quality*, 49(4), pp.812-834.


Purpose: Build an indicator that is:

- Relevant to the TMDL
- Based on monitored changes in load to the extent possible
- Bridges monitoring and modeling by assessing lag time and other effects

TMDL question: What level of **load reduction from 1995** will be necessary to meet water quality standards?




Loads required to meet TMDL Goals




River Input Monitoring (RIM)


- Covers most of the CB watershed
 - 80% of land
 - 60% of load
- Many large WWTP are below RIM stations




Reductions required to meet TMDL Goals




Reductions required to meet TMDL Goals








84% of Expected Reduction is Monitored



Loads and Flow-Normalized Loads




Wastewater is easy to measure and successful





- Percent reduction to WIP
- Expected percent reduction to 2020
- Monitored percent reduction to 2020

Below RIM NPS is about half implemented and is not fully monitored




Above RIM is about half implemented, but monitoring shows only a small reduction




- Percent reduction to WIP
- Expected percent reduction to 2020
- Monitored percent reduction to 2020

Why are monitoring and modeling not showing the same thing?



- Uncertainty in CAST
 - BMPs implemented
 - BMP effectiveness
 - Nutrient applications
 - Watershed response
- Uncertainty in “monitored” loads
- Lag time
- Competing factors such as
 - Climate change
 - Conowingo


Ator, S.W., Blomquist, J.D., Webber, J.S. and Chanat, J.G., 2020. Factors driving nutrient trends in streams of the Chesapeake Bay watershed. *Journal of Environmental Quality*, 49(4), pp.812-834.



- Percent reduction to WIP
- Expected percent reduction to 2020
- Monitored percent reduction to 2020


Lag times

Nitrate in groundwater



Phase 6 CAST documentation

Phosphorus in soils



Conowingo effect


2017/2018 Presentations
to WQGIT, MB, and PSC

Estimated Loads to the Bay with Conowingo Dam and Reservoir at Infill Conditions



Additional Nitrogen Load: 13 million pounds



Additional Phosphorus Load: 1.8 million pounds



Lags and Conowingo account for major differences between Modeling and Monitoring




Estimated Loads to the Bay with Conowingo Dam and Reservoir at Infill Conditions

Additional Nitrogen Load: 13 million pounds




Additional Phosphorus Load: 1.8 million pounds




HOWEVER: These are less bioavailable nutrients and its delivery to Bay is dependent on large storm events. Reduction equivalent to 6 million pounds of Nitrogen and 0.26 million pounds of Phosphorus

Conowingo infill raises the assimilative capacity




→ All else being equal, Conowingo raised loads by 13 million (mostly organic and non-summer) lbs

Conowingo infill raises the assimilative capacity



- All else being equal, Conowingo raised loads by 13 million (mostly organic and non-summer) lbs
- The infill effect can be removed by a watershed reduction of 6 million (more inorganic and summer) lbs



Conowingo infill raises the assimilative capacity





- All else being equal, Conowingo raised loads by 13 million (mostly organic and non-summer) lbs
- The infill effect can be removed by a watershed reduction of 6 million (more inorganic and summer) lbs
- The TMDL water quality is equivalent at 130 pre-infill and 137 post-infill

The water quality change “Seen” by the Bay is greater than the monitoring results by 7 million pounds because of the infill effect



Lags and Conowingo account for major differences between Modeling and Monitoring





Putting it
all
together





The bay has seen 51% of needed reductions




39% is unplanned or unimplemented



10% is lagged
WW not lagged




Proposed Public Indicator





Partnership Product for Data Dashboard

Category	1995	2000	2005	2010	2015	2020
WIP Shortfall	0.9	3.8	6.6	9.4	10.2	11.1
RIM Unimplemented	68.3	53.6	45.4	31.1	28.0	32.1
RIM Unimplemented Conowingo	6.7	6.7	6.7	6.7	6.7	6.7
RIM Expected but not monitored	0.0	0.0	0.0	0.0	0.0	0.0
RIM Lagged	0.0	8.9	17.9	19.3	20.2	13.2
RIM Conowingo Conversion	0.0	4.0	8.3	11.8	11.8	11.4
RIM Monitored	0.0	1.9	-3.3	6.0	8.3	11.6
Below-RIM PS Implemented	0.0	11.2	17.6	20.6	30.0	38.8
Below-RIM PS Unimplemented	37.4	26.2	19.9	16.8	7.4	-1.4
Below-RIM Estimated	0.0	-1.8	-0.6	2.8	6.3	9.7
Below-RIM Lagged	0.0	1.9	5.1	5.1	4.2	2.8
Below-RIM Unimplemented	21.4	21.3	17.0	13.5	10.9	8.9
Tidal Deposition Reduction Realized	0.0	0.5	1.7	3.3	5.2	6.4
Tidal Deposition Reduction Unrealized	7.9	7.5	6.2	4.6	2.7	1.6

Phosphorus Reductions





Phosphorus is mostly implemented, but monitoring results show increases





- Percent reduction to WIP
- Expected percent reduction to 2020
- Monitored percent reduction to 2020


Lags and Conowingo account for more than half of the difference



Lags and Conowingo account for major differences between Modeling and Monitoring




Proposed Public Indicator - Phosphorus



Partnership Product for Data Dashboard

Category	1995	2000	2005	2010	2015	2020
WIP Shortfall	-0.87	-0.68	-0.50	-0.31	-0.21	-0.11
RIM Unimplemented	6.33	5.76	4.28	3.27	2.18	1.85
RIM Unimplemented Conowingo	0.14	0.14	0.14	0.14	0.14	0.14
RIM Expected but not monitored	0.00	1.77	2.10	1.86	2.18	2.58
RIM Lagged	0.00	1.00	2.26	3.17	3.45	2.15
RIM Conowingo Conversion	0.00	0.71	1.62	2.98	2.89	2.29
RIM Monitored	0.00	-2.93	-3.94	-4.94	-4.38	-2.54
Below-RIM PS Implemented	0.00	0.26	0.32	0.84	1.25	1.46
Below-RIM PS Unimplemented	1.57	1.30	1.25	0.73	0.32	0.11
Below-RIM Estimated	0.00	0.48	0.87	0.66	0.70	1.26
Below-RIM Lagged	0.00	-0.40	-0.33	0.10	0.21	-0.34
Below-RIM Unimplemented	1.36	1.28	0.82	0.60	0.46	0.44

Future Work



Future Work

- Add a wastewater category in the RIM loads
- Show Climate and Conowingo increase in reduction expected

Summary

- Indicator summarizes N and P progress toward the TMDL
 - Implemented and realized
 - Implemented but unrealized due to lag
 - Implemented but unrealized due to uncertainty
 - Not implemented
 - Unplanned
- More detailed products for Watershed Data Dashboard
 - Tables for RIM
 - Individual nontidal network Station analyses