Final Stream Restoration Crediting Recommendations from Group 4 & 5





Urban Stormwater Work Group May 19, 2020 www.chesapeakestormwater.net

Thanks to all the talents of Groups 4 and 5


Drew Altland, Chris Becraft, Joe Berg, Ted Brown, Josh Burch, Denise Clearwater, Jason Coleman, Sean Crawford, Barbara Doll, Jens Geratz, Jeremy Hanson, Jeff Hartranft, John Hottenstein, Sujay Kaushal, Scott Lowe, Paul Mayer, Greg Noe, Ward Oberholzer, Art Parola, Durelle Scott, Bill Stack, Joe Sweeney and Jeff White

Key Topics

- 1. Key Floodplain Restoration Concepts
- 2. Comparing LSR and RSB
- 3. Summary of Protocol Adjustments
- 4. Environmental Considerations
- 5. External Review Process
- 6. Comments and Feedback


Evolution of Stream Restoration Design from Channel to the Floodplain





FR-RSB

Floodplain Restoration-Raising the Stream Bed




Comparing Floodplain Restoration Strategies

	LSR Legacy Sediment Removal	RSB Raised Stream Bed		
Strategy	"Lower the Floodplain"	"Raise the Stream"		
Design Approach	Legacy sediments are removed from the floodplain, which reduces bank heights, expands hyporheic exchange, and reconnects stream to its floodplain/aquifer	Raise the stream invert either by (a) filling incised channels and/or (b) installing riffle/grade control practices to effectively lower bank heights and access the floodplain more frequently		
Boundaries and Zones	Both share common zones such as BEZ, EHZ and FTZ, but use different indicators and field methods to define their precise vertical and lateral boundaries			


Agreement on Standardized Terms and How Zone Boundaries are Defined/Measured

BEZ	Bank Erosion Zone	LS	Legacy Sediment		
BSR	Big Spring Run	LSR	Legacy Sediment Removal		
EHZ	Effective Hyporheic Zone	NCD	Natural Channel Design		
FR	Floodplain Restoration	OGS	Outfall and Gully Stabilization		
FTZ	Floodplain Trapping Zone	P-#	Protocol 1, 2 or 3		
HA	Hyporheic Aquifer	PS	Prevented Sediment		
HB	Hyporheic Box ¹	RSB	Raised Stream Bed		
HEZ	Hyporheic Exchange Zone	RSC	Regen. Stormwater Conveyance		
as originally defined in Section 2.2 in USR EPR (2013)					


BEZ, EHZ and the FTZ



Floodplain Restoration: Legacy Sediment Removal




Floodplain Profiles, before and after restoration





Floodplain Restoration Raised Stream Bed



Comparing Floodplain Restoration Strategies- II

	LSR	RSB			
	Legacy Sediment	Raised Stream Bed			
	Removal				
Project Qualifying	Project EHZ and FTZ boundaries based on field investigations Avoid extended ponding/inundation of the floodplain				
Conditions	 Legacy sediment deposits are present LS removal primary restoration technique Floodplain reconnected to valley aquifer 	 Upstream and downstream grade controls to maintain intended stream invert Maintain pre-restoration baseflow characteristics 			
Floodplain	Restore historical floodplain	Wider range of potential			
Plant Community	plant community (often wet meadow complexes)	floodplain habitat outcomes, e.g., could also be forest or scrub-shrub wetlands			

Comparing Floodplain Restoration Strategies- III

Protocol Adjustments				
Protocol 1 Adjustments	Use one of the following options: Option 1: Divide the Bank Erosion Zone (BEZ) into two components: Remaining low-bank sediments and removed legacy sediments from the higher bank. Remaining sediments are subject to the 50% discount, whereas removed sediments are not subject to any discount (i.e., 100% credit). Option 2: Base the credit on actual monitoring data acquired for the project, using new Group 3 methods			
Protocol 2: Adjustments Protocol 3 Adjustments	The dimensions of the EHZ are defined differently across the stream and floodplain for each strategy, but otherwise apply the same methods Both approaches use the same methods			

Guiding Principles

- Ensure tweaks are Phase 6 watershed model compatible (e.g., delivery, new stream source)
- Retain the integrity of the pollutant removal protocols, but tweak based on:
 - Better science to define removal parameters (e.g., unit denitrification rate)
 - Field testing of most sensitive parameters in load calculations
 - More defensible methods to define boundaries over which the removal processes operate

Summary of Protocol 2 Consensus

For FR-LSR Projects:


- Replace the existing Hyporheic Box with an "Effective Hyporheic Zone" whose lateral dimensions are defined by surface, groundwater and wetland indicators
- EHZ Indicators are measured in the field and shown on post-construction plans
- The EHZ is typically shallow, often only 9 to 18 inches deep at most projects.

For FR-RSB Projects

- EHZ boundaries are defined by plan form geometry of the valley bottom, such as the width of outer meander bends, aquifer elevations, and associated floodplain wetlands
- Appropriate field indicators to measure them are being developed by group

For ALL FR Projects:

- Update the existing denitrification rate to reflect the latest science, and convert it from volumetric to aerial units
- Adjust the base denitrification rate for site factors, such as streamflow, floodplain soils and hyporheic conductivity
- Eliminate the bank height ratio requirement, since it does not apply to low-bank FR projects



New Denitrification Rate

 2.69×10^{-3} lbs NO_3/sq ft/year

- Based on comprehensive lit review
- Difference in median nitrate uptake rates from Newcomer-Johnson et al. (2016)
- 30% of uptake is from denitrification (Mulholland et al 2008)

The Parola Equation

 $N \, credit = (Base \, Rate) \, (EHZ) \, (A_f) \, (V_f) \, (B_f)$

Where:

N Credit = P-2 N reduction (lbs/yr)

Base rate= average denitrification rate (lbs/square foot/year)

EHZ = Area of Effective Hyporheic Zone (square feet)

Af = Aquifer Conductivity Reduction factor (0-1)


Vf = Vegetation Reduction factor (0-1)


Bf = Baseflow Reduction factor (0-1)

Discounting Factors to Base Denitrification Rate

Table 10: Site Spec	Table 10 : Site Specific Discount Factors for Adjusting the Denitrification				
Rate (Parola et al, 2019)					
$HEZN \ credit = (Base \ Rate) (EHZ) (B_f) (S_f) (A_f)$					
Baseflow Reduction Factor		Soil Saturation Reduction		Aquifer Conductivity	
(D)		Factor ¹ (S _f)		Reduction Factor ² (A _f)	
(B_f)					
Perennial baseflow	1.0	Channel	1.0	Gravel, sandy gravel	1.0
				or clean sand	
Baseflow in all but	0.75	Herbaceous or scrub	1.0	Silty sand or silty	0.6
late summer/fall		shrub wetland		gravel loam	
Baseflow in	0.50	Forested wetland	0.6	Silt	0.2
winter/spring					
Baseflow only during	0.25	Non-wetland forest	0.2	Clayey silt	.05
wet seasons					
Flow only during	0.10	Non-wetland herb.	0.1	Clay	.001
runoff events		Scrub shrub			

Protocol 3: Floodplain Trapping






Summary of Areas of Consensus for P-3

- The credit should be based on the difference in load reduction based on a before and after application of P-3 to individual projects.
- Hydraulic modeling defines the extent of reconnection boundaries for the FTZ, based on critical floodplain flow velocities where sediment trapping and filtering can be expected.
- Retain the one-foot max elevation above the floodplain as the upper limit for effective runoff treatment in the FTZ, unless a higher elevation is justified by floodplain H&H modeling.
- Multiply the FTZ by the appropriate wetland removal rate established for floodplain wetland restoration projects, as defined by NTW EPR to determine project load reduction.
- Rely on downstream flow methods to estimate annual volume of storm runoff diverted into the floodplain for treatment
- Recommend standard methods for defining baseflow channels, separating baseflow from storm flows and processing appropriate USGS flow gage data

Figure E-1. Flow Duration Curve for calculating floodplain treatment (Altland 2019).

Develop Regional Flow Duration Curve(s) from Stream Gage Data – 15 Minute Interval



Non-Tidal Wetland Removal Rates

Table 13. Floodplain Wetland Removal Rates in Prior CBP Expert Panel Reports				
Wetland BMP	Pollutant Removal Rate (compared to pre-restoration)			
Category	Total N	Total P	TSS	
NTW Restoration	42%	40%	31%	
NTW Creation	30%	33%	27%	
NTW Rehabilitation	16%	22%	19%	
¹ as outlined in expanded lit review and recently approved EPR (NTW EP, 2020)				

- Restoration: Wetland absent or degraded. Hydric soils present
- Rehabilitation: Wetland present w/ degraded function
- Creation: No wetland present, no hydric soils present

Other Improvements

Design Examples

Step 1. Define the Extent of the EHZ.

Calculate the area of the restored floodplain:

• 1,000 ft x 200 ft = 200,000 sq ft

Calculate the area of the restored channel:

• 1,000 ft x 5 ft = 5,000 sg ft

Reduce by 10% to account for the floodplain area that is perched more than 18" above the low flow water surface or streambed elevations:

• 200,000 sg ft x 0.9 = 180,000 sg ft

Step 2. Apply the Denitrification Rate to the EHZ


- 180,000 sq ft x 0.00269 lbs/sq ft/year = 484 lbs NO₃/year
- 5,000 sq ft x 0.00269 lbs/sq ft/year = 13.45 lbs NO_3 /year

Step 3. Apply the Site Specific Discount Factors

The site has perennial baseflow, <u>sandy-gravel</u> hyporheic soils and an herbaceous wetland plant community throughout the restored floodplain. Therefore, for the floodplain area, each factor is 1.0 and no discount is applied. The factors for the channel area would also all be 1.0.

Other Improvements

 Site Monitoring and Field Verification





Improvements

Future Research Priorities:


- Long-term interdisciplinary research studies on nutrient and sediment dynamics
- Shorter-term research studies on best practices for mitigating unintended environmental impacts
- Defining and testing metrics for measuring functional uplift/loss

Break for Questions



Get current at: www.chesapeakestormwater.net

Environmental Considerations



We all have a lot of biases when it comes to stream restoration

















Unintended Environmental Consequences of Stream Restoration Practices

Project Stream Channel

- Depleted Dissolved Oxygen
- Iron Flocculation
- Warmer Summer Stream Temperatures
- More Instream Primary Production
- Turbidity During Project Construction
- Initial Decline in Benthic IBI

Floodplain/Downstream

- Project Tree Removal
- Post Project Tree Loss
- Vector for Invasive Plant Species
- Shift in Wetland Type/Functions
- Increased Flooding
- Initial Decline in Downstream IBI
- Upstream Blockage for Aquatic Life

Severity of impacts is related to:

- Inadequate project assessment
- Site-specific factors
- Exposure to extreme flows
- Care taken in project location, design and construction
- Use of specific best practices to minimize impacts


General Notes on Impacts

- Impacts need to be considered in relation to the stressors measured in a comparable unrestored urban stream/floodplain system
- Short-term adverse impacts are common during and shortly after construction, followed by project adjustment and recovery over several years

Best Practices (BP) for TMDL Stream Restoration Projects

- Choosing the Right Stream Restoration Projects
- Project Design Principles
- Good Construction Practices
- Post-Construction Practice for Inspecting,
 Verifying and Maintaining Projects

Upland Alternatives to Stream Restoration







BP for Project Assessment and Design

- Assess sources of stream and floodplain impairment
- Avoid restoration projects at sites where stream and floodplain metrics indicate good or excellent condition.
- Forests surveys to minimize tree clearing
- Habitat functions assessed prior to design, especially when quality stream/wetland resources are suspected to be present
- Special protection for freshwater mussels and their host fish

BP for Project Assessment and Design

- All constructed instream structures should be designed to ensure aquatic life can safely pass
- Avoid creating stagnant pools in stream channels.
- Avoid designs that rely on excessive bank armoring and respect limits adopted by Group 3
- Avoid long-term inundation or pooling over the floodplain
- H&H modeling to define how 100-year floodplain elevations change in response to projects
- Investigate soils for toxics at brownfield floodplain sites

BP During Project Construction

- Reduce the use of "iron-rich" in-stream construction materials
- Minimize additions of organic matter when raising the stream bed
- Minimize removal of mature trees and protect hem during construction
- Minimize compaction of stream bed, banks and floodplain by construction equipment
- Work "in the dry" during construction to reduce sediment impacts
- Recycle wood from any trees cleared during construction


BP for Post-Construction Phase

- Verify that projects meet their functional performance objectives
- Use Group 1 methods to verify floodplain reconnection functions years after initial permit expires
- Focus on indicators for project failure:
 - Pre-restoration baseflow conditions
 - Bank heights that support floodplain reconnection
 - Desired targets for restored floodplain plant community
- Post-construction invasive species management
- Adjust structures to lower water elevation to prevent unacceptable floodplain inundation or pooling

Ideal pathway for going forward



- **June 19th Deadline**: External Comment Period for USWG/SHWG/Others
- Seek USWG Approval in July
- Expanded review/approval @ WTWG/WQGIT in August/Sept
- Develop unified Summary in Fall (no further review)
- State by state outreach (upon request)
- WQ and Habitat groups to possibly fund workplan to do priority research on effect of best practices for restoration practices
- Further CSN work on practice resilience to climate change
- BIG party on the Pataspco



Comments and Feedback



Photo Credit: G. Noe, USGS